

## CLAIMS

What is claimed is:

- 5           1.       A trailer for delivering asphalt material to a paving machine comprising:  
a trailer bed for holding asphalt material;  
a trailer frame having at least one axle; and  
at least one hinge arm having a length separating two end portions wherein the  
first end portion is fixed to said trailer bed and the second end portion is mounted to said  
10       axle, and wherein said hinge arm is disposed at a non-vertical angle between said trailer  
bed and said trailer frame.
2.       The trailer of claim 1 wherein the length of said hinge arm is greater than  
the vertical distance between said trailer bed and said axle.
- 15           3.       The trailer of claim 2 wherein said trailer includes at least two parallel  
hinge arms.
4.       The trailer of claim 2 wherein said trailer includes at least two axles.
- 20           5.       The trailer of claim 1 wherein said axle is mounted below said frame.
6.       The trailer of claim 1 wherein said second end portion is pivotably  
mounted to said axle.

7. The trailer of claim 1 wherein said trailer is a full length dump trailer.

8. The trailer of claim 1 wherein said trailer is a semi-length dump trailer.

5 9. The trailer of claim 1 wherein said trailer is a full frame trailer.

10. The trailer of claim 1 wherein said trailer is a half frame trailer.

10 11. The trailer of claim 1 wherein said trailer further comprises a mud flap  
10 bracket substantially parallel to said hinge arm attached to said trailer bed between said  
hinge arm and the end of said trailer bed.

12. A hinge positioned near the rear of a trailer for delivering asphalt material  
to a paving machine comprising:

15 a body member having a bed end and a frame end;

wherein said bed end is fixed to the dump bed of said trailer; and

wherein said frame end is pivotably mounted to the frame of said trailer between  
the rear of said trailer and said bed end.

20 13. The hinge of claim 12 wherein said frame end is mounted to said frame by  
at least one axle.

14. The hinge of claim 13 wherein the length of said body member is greater than the vertical distance between said dump bed and said axle.

15. A mud flap unit positioned near the rear of a trailer for delivering asphalt material to a paving machine comprising:

a bracket having a bed end and a flap end;

wherein said bed end is fixed to the dump bed of the trailer; and

a mud flap mounted to said flap end between the rear of the trailer and said bed end.

16. The mud flap unit of claim 15 wherein said bracket is substantially parallel to a hinge arm connecting the dump bed to the frame of the trailer.

17. A trailer for delivering asphalt material to a paving machine comprising:

a trailer frame having a back portion;

a trailer bed mounted to said trailer frame for holding asphalt material wherein said trailer bed is movable between a lowered position and a raised position; and,

at least one hinge arm extending between said trailer bed and said trailer frame wherein said hinge arm operates to move said trailer bed upward and backward relative to

said trailer frame when said trailer is moved between said lowered position and said raised position.

18. The trailer of claim 17 wherein said hinge arm is disposed at a non-vertical angle between said trailer frame and said trailer bed.

19. A method for delivering asphalt material from a trailer to a paving machine hopper comprising:

5 providing a paving machine having an asphalt material hopper with a front panel;

providing a trailer having a bed portion containing asphalt material and a frame portion;

aligning said paving machine with said trailer; and,

10 delivering asphalt material to said hopper by moving said bed portion upward and towards said hopper.

20. The method of claim 19 wherein said trailer includes a hinge member attached to said bed portion and said frame portion.

21. The method of claim 20 wherein said hinge member is disposed at a non-vertical angle between said bed portion and said frame portion.

22. The method of claim 19 wherein said bed portion includes a spill guard.

23. The method of claim 22 wherein said delivery step further comprises moving said spill guard over said front panel.